

SUBJECT :- Renovation of Film Store Room near unloading dock in central dairy DMS
During 2012-13

Sealed item rate quotations are invited for the work mentioned above and same shall be received from the working/ willing contractors up to 2.45 P.M. and shall be opened at 3.00 P.M. on 16.4.2012 in the office of Assistant Engineer (Civil) R.NO.43 in the presence of indenting contractors. Contractors should satisfy themselves with the scope of work before quoting their rates . Quotationers are requested to send the same by post or put in the tender box kept in the reception hall Administrative Block Delhi Milk Scheme New Delhi

S.NO.	Description of Items	Qty.	Unit	Rate	Amount
1.	Dismantling tiled/ ply board/ ACC roofing with battens etc .complete including stacking of serviceable material and disposal of unserviceable material within 50 m lead.	60.00	sqm	----	-----
2.	Brick work with F.P.S. brick of class designation 75 in superstructure above plinth level up to floor V level in all shapes and size in cement mortar 1:4(1 cement: 4 coarse sand)	7.00	cum	-----	-----
2	. 15 mm cement on rough side of single or half brick wall of mix 1:4 (1 cement : 4coarse sand)	100.00	sqm	-----	-----
4.	Finishing wall with Premium Acrylic Smooth exterior paint with silicone additives of required shade , New work (two or more coat applied @ 1.43 ltr/10 sqm over and including base coat of water proofing cement paint applied @2.20 kg/10sqm	100.00	sqm	-----	-----
5.	Providing and fixing UV stabilized fiberglass reinforced plastic sheet roofing up to any pitch including fixing with polymer coated Jor L hooks, bolts and nuts 8mm dia GI plain/ bitumen washer complete but excluding the cost purlin, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3 % ultra-violet stabilizer in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to 10192 and IS 12866. The sheet shall be translucent, clear or pigmented, textured or smooth as specified 2mm thick flat	30.00	sqm	-----	-----

6. Providing and laying four course water proofing treatment with bitumenfelt over roofs consisting of first and third course of blown bitumen 85/25 or 90/15 conforming to IS :702 applied hot @ 1.45 kg per square metre of area for each course , second course of roofing felt type 3 grade -1 and fourth and final course of stone grit 6 mm and down size or pea-sized gravels spread at 6 cubic diameter per square meter including preparation of surface but excluding grading complete with bitumen felt type 3 grade


50.00 sqm ----- -----

7 Kota stone slab flooring over 20 mm average thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand) ,25 mm thick

5.0 sqm ----- -----

Tendered Amount -----

CONDITIONS :- AS ENCLOSED



CONDITIONS

1. Work will be executed as per direction of engineer in charge.
2. 1% water/electric charges will be recovered from the gross amount of bill, if the work is executed within DMS premises.
3. Rate so quoted will be valid up to March 2013.
4. The work will be executed as and when asked for which a separate work order will be issued on the basis of approved rate term and conditions. 1st class brick will be used instead of class designation 75 bricks
5. No any escalation will be considered in respect of hike in prices of labour and materials till the rate is valid.
6. No any extra payment will be made for any hidden item
7. Work will be executed within 45 days after issue of work order failing which a penalty of Rs. 100/per day will be deducted from the bill till the completion of work.
8. Earnest money of Rs 1796/ in shape of DAC in favour of GM (DMS) of a schedule bank to be deposited, without earnest money quotation will not be considered

Signature of contractor _____

Name and address _____



Assistant Engineer (civil)